
Technical Report 1

The Center for Sustainable Landscapes for The Phipps Conservatory and Botanical Gardens – Pittsburgh, PA



Daniel Zartman

September 23, 2011

Construction Option

Advisor: Dr. Robert Leicht

Penn State AE Senior Thesis

Executive Summary

Technical Report 1 is a synopsis of the scope of work being performed and contractual organization of the construction of the *Center for Sustainable Landscapes (CSL)* for *The Phipps Conservatory and Botanical Gardens* by Turner Construction. The *Center for Sustainable Landscapes (CSL)* project is primarily the development of a currently undeveloped portion of the Phipps Conservatory campus in Schenley Park, Pittsburgh PA. Included in the project is the demolition of a small portion of warehouse and the new construction of a 3 story, 24,350 SF mixed use educational facility and office building.

With the construction of the CSL, the Phipps Conservatory will add to its repertoire of iconographic buildings by becoming a home to one of the most sustainable commercial buildings in the nation. The CSL is attempting to meet the Living Building Challenge issued by the ILBI, and the Sustainable SITES certification issued by the Sustainable Sites Initiative. By meeting the Living Building Challenge objectives, the building will also exceed LEED Platinum certification. As a result, the biggest challenge faced by this project is the successful achievement of all 3 prestigious sustainable goals.

As a result of the sustainable focus, a plethora of unique construction materials and techniques are used on this project. Some of the sustainable features include: a green roof, passive and active HVAC systems, onsite power generation, onsite gray water retention, and a building automation system for the control of the dynamic building elements and power consumption. Due to the heavy emphasis on sustainability, increases in upfront construction costs were seen as an exchange for lower life-cycle costs.

Sustainable challenges aside, the construction of the CSL will not present any additional construction abnormalities. The Phipps Conservatory is a relatively experienced owner that allows the project schedule to be flexible to changes. As a result, the project schedule is not compressed and is of an average duration for the project size. Traditional construction and contractual practices used on the project include: construction of a cast-in-place concrete substructure and structural steel superstructure, the project delivery method used was design-bid-build with a lump-sum contractual agreement. The project budget is approximately ten million dollars. The project is managed by three full time onsite personnel and two office managers. The project site, relative to the building footprint, does not present any unique scheduling or site lay out issues.

Table of Contents

Executive Summary	1
Table of Contents	2
Synopsis of Project Schedule Summary	3
Project Schedule Summary	4
Building Systems Summary	5
Project Cost Evaluation	11
Site Plan of Existing Conditions	13
Phase 1 Site Layout Plan	14
Phase 2 Site Layout Plan	15
Phase 3 Site Layout Plan	16
Local Conditions	17
Client Information	18
Project Delivery System	19
Staffing Plan	21
Appendix A: RS Means Square Foot Estimate	
Appendix B: RS Means Assemblies Estimate	

Synopsis of Project Schedule Summary

Design development for the project began in the summer of 2008 with the selection of *The Design Alliance Architects* of Pittsburgh, PA. The Construction Documents were started in January of 2010 and were completed June that year. The Bid Phase lasted for a 2 month period from the beginning of July through the end of August. Upon award of the project, Turner Construct finalized the Project Procurement phase with subcontractor buy-outs and purchase orders. The Notice to Proceed occurred in the beginning of January 2011.

The Construction Phase of the project came in with the New Year in January 2011. Demolition of the existing warehouse occurred throughout January and February prior to the start of construction in April. Construction on the CSL began on April 21, 2011 with the excavation of foundations and the construction of the substructure. Substructure construction continued through to the beginning of July with the completion of the CIP concrete structural walls. Erection of the Superstructure began just prior to the ending of substructure construction on June 29, 2011. As the erection of the Superstructure continues, overlapping work begins to take place with the installation of roofing in order to meet the watertight milestone prior to the start of the colder season and winter. Currently, the exterior envelope is on schedule to be completed in the beginning of November. As the structure nears completion, the ramping up of Mechanical, Electrical, Plumbing, and Fire Protection (MEPFP) trades during rough installation will start and continue throughout the winter slowing transitioning into interior finishes installation and ending with testing and commissioning of the newly installed systems. Project completion is currently scheduled for April 20th, 2012.



Figure 1 - This photo was taken on September 7th, 2011. Construction crews were working on completion of the 2nd and 3rd floor's Slab on Deck (SOD).

Project Schedule Summary - Center for Sustainable Landscapes

ID	Task Name	Duration	Start	Finish	Qtr 3, 2008	Qtr 4, 2008	Qtr 1, 2009	Qtr 2, 2009	Qtr 3, 2009	Qtr 4, 2009	Qtr 1, 2010	Qtr 2, 2010	Qtr 3, 2010	Qtr 4, 2010	Qtr 1, 2011	Qtr 2, 2011	Qtr 3, 2011	Qtr 4, 2011	Qtr 1, 2012	Qtr 2, 2012	Qtr 3, 2012	Qtr 4, 2012
1	Design Development	393 days	Tue 7/1/08	Thu 12/31/09	Design Development																	
2	Construction Documents	129 days	Fri 1/1/10	Wed 6/30/10	Construction Documents																	
3	Bid Phase	44 days	Thu 7/1/10	Tue 8/31/10	Bid Phase																	
4	Procurement Phase	88 days	Wed 9/1/10	Fri 12/31/10	Procurement Phase																	
5	Notice To Proceed	0 days	Mon 1/3/11	Mon 1/3/11	Notice to Proceed																	
6	Demolition	20 days	Mon 1/3/11	Fri 1/28/11	Demolition																	
7	Site Work	257 days	Thu 4/21/11	Fri 4/13/12																		
8	Sitework - Driveway & South	257 days	Thu 4/21/11	Fri 4/13/12	Sitework - Driveway & South																	
9	Sitework - Northwest	246 days	Fri 5/6/11	Fri 4/13/12	Sitework - Northwest																	
10	Sitework - Northeast	222 days	Thu 6/9/11	Fri 4/13/12	Sitework - Northeast																	
11	Substructure	55 days	Thu 4/21/11	Wed 7/6/11																		
12	Over Excavation and Lean Fill	49 days	Thu 4/21/11	Tue 6/28/11	Over Excavation and Lean Fill																	
13	CIP Footings & Piers	36 days	Thu 4/28/11	Thu 6/16/11	CIP Footings & Piers																	
14	CIP Walls	49 days	Fri 4/29/11	Wed 7/6/11	CIP Walls																	
15	Superstructure	62 days	Wed 6/29/11	Thu 9/22/11																		
16	CIP Concrete	25 days	Fri 8/5/11	Thu 9/8/11	CIP Concrete																	
17	Steel Erection	62 days	Wed 6/29/11	Thu 9/22/11	Steel Erection																	
18	Enclosure	68 days	Mon 8/8/11	Wed 11/9/11																		
19	Façade	35 days	Thu 9/22/11	Wed 11/9/11	Façade																	
20	Roofing	50 days	Mon 8/8/11	Fri 10/14/11	Roofing																	
21	Watertight	0 days	Wed 11/2/11	Wed 11/2/11	Watertight																	
22	MEP/FP Rough-In	69 days	Mon 8/15/11	Thu 11/17/11																		
23	Rough Ins - Above Ceiling	69 days	Mon 8/15/11	Thu 11/17/11	Rough Ins - Above Ceiling																	
24	Rough Ins - Equipment	56 days	Mon 8/15/11	Mon 10/31/11	Rough Ins - Equipment																	
25	Interior Finishes	103 days	Tue 9/27/11	Thu 2/16/12																		
26	Interior Finishes - Ceilings	89 days	Tue 9/27/11	Fri 1/27/12	Interior Finishes - Ceilings																	
27	Interior Finishes - Flooring	103 days	Tue 9/27/11	Thu 2/16/12	Interior Finishes - Flooring																	
28	Interior Finishes - Partitions	35 days	Mon 10/31/11	Fri 12/16/11	Interior Finishes - Partitions																	
29	Testing and Commissioning	52.81 days	Wed 2/1/12	Fri 4/13/12	Testing and Commissioning																	
30	Occupancy	0 days	Fri 4/20/12	Fri 4/20/12	4/20																	

Project: Project Schedule without Date: Thu 9/22/11

Task

Split

Milestone

Summary

Project Summary

External Tasks

External Milestone

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

Deadline

Progress

4

Building System Summary

Building Systems Summary		
Yes	No	Work Scope
x		Demolition
x		Structural Steel Frame
x		Cast-in-place concrete
	x	Precast Concrete
x		Mechanical System
x		Electrical System
	x	Masonry
x		Curtain Wall
x		Support of Excavation
x		LEED Certification
X		Living Building Certification
X		Sustainable SITES Certification

Demolition –

Neighboring the CSL building footprint is the existing B & G Warehouse. During the site development stage, selective demolition of a portion of the single story CMU warehouse occurred. The existing warehouse is approximately 16,000 SF in size, of which 7,500 SF will be demolished. During the demolition process, no hazardous materials were encountered. The remaining portions of the masonry warehouse will be repointed and painted. In Figure 2 below, the area highlighted in red denotes the portion of the building that was demolished.



Figure 2 – A bird’s eye view of the project site from the north, the area in red is the portion of the warehouse that was demolished.

Structural Steel Frame –

The primary structural building material for the CSL is structural steel. Beam sizes consist primarily of type W12 and W16 made of ASTM A992 steel with a yield strength of 50 ksi. Column sizes consist primarily of HSS 4x4 and HSS 6x6 shapes made with ASTM A500 Grade B with a yield strength of 36 ksi. The CSL is unique in that it is being constructed against a steeply sloped hill. The building’s structural system benefits from this design in that it requires little lateral bracing. Lateral loads that are imposed on the frame are channeled back into the concrete foundation/retaining wall (highlighted in red on Figure 3) that extends to the bottom of the 3rd story and span across 4 of the 8 structural bays in the building.

The crane used for the erection of steel was a Terex Model T560, a 50 ton hydraulic truck crane. The cranes location changed with the progression of construction; moving from the western portion of the site to the eastern portion.





Figure 3 – First Floor plan provided by The Design Alliance Architects. Area highlighted in red is a CIP concrete wall approximately 28 ft height, extending to the bottom of the 3rd floor.

Cast-in-Place Concrete –

Cast-in-place (CIP) concrete was utilized as a secondary structural component on numerous aspects of the project. Specifically, cast-in-place concrete was used as for foundation footings and walls, a column in the atrium, the atrium stair, Slab on Grade 1st floor, Slab on Deck above grade floors, and a few select concrete walls. Metal reusable wall forms were used for all CIP concrete with the exception of the atrium column and stair; both of which are currently being considered to be constructed out of an alternative material for constructability reasons. Above grade SODs are constructed of 2" composite metal decking with a 3-1/2" concrete slab placed on top of welded wire fabric reinforcing. Due to accessibility reasons, placement of the majority of concrete required the use of a concrete pump. In addition, all slabs required the use of Lightweight concrete.

Mechanical System –

Perhaps one of the most technically advanced systems in the CSL, the mechanical system is a combination of passive and active design. The majority of the building is heated and cooled by one variable air volume AHU supplying a maximum of 12,400 CFM. A geothermal ground source heat pump and enthalpy wheel was installed in order to further reduce the energy load imposed by the AHU. Housed on the north side of the first floor, the mechanical room supplies the AHU with preconditioned refrigerant from the closed loop geothermal system and air pressure to the dry pipe fire suppression system. In addition, other unique design features include a raised floor system for the distribution of supply air, thermal radiant floor heating to provide supplementary heat, and a green roof for increased thermal mass to stabilize the heating and cooling loads. Unconditioned space, such as the large atrium, remains entirely heated and cooled naturally through passive design. Two diagrams depicting the air flow in the passively design spaces are pictured below.



Figures 4A & 4B – Provided by The Design Alliance Architects, images depict the natural ventilation of the passively designed spaces.

Electrical System –

Due to the new facilities close proximity to the Phipps Conservatory; a 600 amp 3 phase electrical service connects the new CSL with the existing neighboring facilities. Standard voltages of 120/208 and 277/480 are distributed as needed throughout the building via the raised access floor system. A unique aspect of the electrical system is the large amount of power generated onsite. A current goal for the building is to maintain net-zero energy use on an annual basis. Onsite generation is primarily composed of three 36 kW solar panel arrays, but also utilizes vertical axis wind turbines to supplement demand. Furthermore, the utilization of a Direct Digital Control Building Management System will provide system feedback for optimal energy efficiency. Aside from having onsite variable power generation, no redundant electrical systems are being installed.

The lighting system is a hybrid of energy efficient LED, florescent lighting, and natural lighting design. The CSL is equipped with a building automation system that controls the amount of natural light that enters a space through a system of moveable sunshades. The dynamic shading system for this building enables the shades to move over the course of a day and year to control the amount of natural light entering the space. The dynamic shading system also maximizes or minimizes the thermal gains when appropriate to reduce the cooling and heating loads.

Exterior Wall Assembly –

The exterior wall assembly design fully embodies the sustainable design motifs of the project. Depicted in Image 6, is a cross section of a portion of a typical exterior wall. 2 types of exterior glazing are used, all of which are Sealed Clear Insulating Glass Units (IGU) with multiple Low-E suspended films. Significant variations include; thicknesses of 1-1/2", 1-1/4", and R-Value of 10.87, 7.69 respectively.

Wall Assembly from Outside Surface to Inside Surface

1. Reclaimed Barn Wood
2. Wood battons
3. Air Space
4. 2" Rigid Board Insulation
5. Weather Barrier
6. 5/8" Glass-Mat Gypsum Sheathing
7. 8" Metal Stud Framing
8. 8" Fiberglass Insulation
9. 5/8" Gypsum Wall Board




Figure 6 – Cross Section of Exterior wall

Excavation Support System –

In order to properly protect the adjacent Phipps Conservatory greenhouses and to stabilize excavation, the utilization of a rock tieback system was used on the north side of the building. During construction, the internal support from the tiebacks will provide construction workers with a clear space to operate. Once complete, the tieback system will remain in place as a permanent component of the building structure. For this project, no dewatering system was required.

Sustainable Achievements –

The CSL is going to set a high standard for sustainability on a national scale. Currently, this project is attempting to meet multiple sets of standards including; LEED Platinum, Living Building Challenge, and SITES Certification for Landscapes. In order to accomplish these goals several design and construction practices have been directly implemented.

Implemented Sustainable Designs and Technologies:

- Passive building design strategies that minimize energy usage through maximizing natural lighting and heating and minimizing cooling
- Direct Digital Control Building Management System will monitor and control dynamic passive systems for optimal efficient operations
- Demand Controlled Ventilation, consisting of CO₂ sensors located in rooms to determine the minimum amount of outside air ventilation required per occupancy level.
- High thermal mass façade and low emissivity windows
- Ground source geothermal heat pump used to capture an estimated 70% of heating and cooling energy
- Desiccant energy recovery wheel (Enthalpy Wheel) pre-cools and pre-heats outside air as needed to further reduce cooling and heating loads.
- Solar Photovoltaics and Vertical Axis Wind Turbines for onsite electricity generation.
- Sustainable materials meeting the Regional , Recycled, and salvaged content requirements
- Green Roof to reduce storm water runoff and to reduce heating and cooling loads on the HVAC system
- Rainwater harvesting for reuse as gray water
- Lagoon System to capture overflow from rainwater harvesting cisterns and permit it to enter the environment in a natural manner
- Permeable paving for natural filtration of water into ground
- Constructed Wetland to treat all sanitary water from CSL site

Project Cost Evaluation

Actual Construction Cost –

Construction Cost:	\$ 10,000,000	\$ 410 /SF
--------------------	---------------	------------

The entire contracted value for construction was \$10 million, which was approximately \$410 per SF (value based on the total gross square footage of building). Exclusions from construction cost include; land cost, and permitting.

Actual Building System Costs –

Mechanical/Plumbing System Cost:	\$ 600,000	\$ 25 /SF
Electrical System Cost:	\$ 1,000,000	\$ 41 /SF
Structural System and Facade Cost:	\$ 1,700,000	\$ 70 /SF
Fire Protection System Cost:	\$ 75,000	\$ 3.10 /SF

The building system costs expose the actual building systems costs. The prices are expressed as lump-sum and square foot values. The scope of work includes the supply and installation of each system. The structural system includes; substructure, superstructure, and façade.

Square Foot Estimate –

Square Foot Estimated Cost:	\$ 3,859,500	\$ 158.50
-----------------------------	--------------	-----------

The Square Foot Estimate was performed using cost data from RS Means Costworks, an online data base of pricing and cost estimation software. The square foot estimate revealed that the actual project costs for the CSL were significantly higher than the estimated value. This increased cost is a result of the high amount of money invested in technology and intelligent design.

Square Foot Estimate Assumptions:

It was assumed that the building type that most accurately represented the CSL was a College Classroom building, 2-3 Stories in height with a decorative concrete block façade and a structural steel frame. Project specific inputs include: 520 LF of perimeter wall, 24350 SF of floor area, 14 ft story height, and a project location in Pittsburgh PA being built in 2011. Additional equipment added to estimate includes a hydraulic, 3 stop elevator. Contractor's OH&P was estimated to be a generous 6%. Architectural Fees were estimated to 3%. Excluded from this cost is site work. See Square Foot Estimate in Appendix A for more the estimate.

Assemblies Estimate –

Assembly Estimate Mechanical/Plumbing Cost:	\$ 762,400	\$ 31 /SF
Assembly Estimate Electrical Cost:	\$ 999,643	\$93 /SF
Assembly Estimate Fire Protection Cost:	\$ 80,700	\$ 3.30

The Assemblies Estimate was performed using RS Means Costworks. The values for the assemblies' costs are expressed as lump-sums and square foot costs.

Results:

In the Assemblies estimate, the RS Means generic system assumptions do not adequately reflect the actual Mechanical systems specified in the plans and specification. The Mechanical/Plumbing system was estimated to cost an additional 27% more than the actual cost for design and installation. Estimated costs of a raised floor system are not available as an assembly in RS Means, resulting in a significant difference to the scope of work estimated. Furthermore, RS Means also does not provide pricing data for gray water recycling cisterns and other sustainable design features. Effectively, due to the above average level of intricacies built into the sustainable system designed, RS Means was not able to provide an accurate Mechanical/Plumbing system cost.

RS Means did estimate the cost of the Electrical system and Fire Protection systems accurately, with a cost variation of less than 1% and 7% respectively. RS Mean's Assemblies Cost Data for these systems more accurately reflected the actual systems installed than that of the mechanical system.

Site Plan Description

Existing Conditions –

Developed from the original Existing Conditions site plan C100 provided by the Design Alliance Architects, the ensuing Existing Conditions plan is a layout of the undeveloped site prior to the start of construction. This site plan reflects the site layout for temporary facilities, parking, access roads, onsite utilities (above and below ground), and neighboring buildings. Flow of construction vehicular traffic is represented with large yellow arrows. Pedestrian traffic is not depicted as there are no pedestrian walkways on or near the project site. Utilities depicted in gray are future utilities that will be installed during construction.

Phase 1 –

Phase 1 construction plan is developed from the same Existing Conditions plan, C100, but does not reflect the existing utilities. The original contractor layout prescribed the utilization of the existing warehouse for temporary office space. Technologies demanded by projects teams exceeded those provided by the warehouse, as a result, the placement of a job trailer in an isolated corner of the warehouse was prescribed. Temporary power is shown on the north site of the future building footprint. During this phase demolition of a portion of the existing B & G Warehouse will occur, the area of demolition is depicted in red. Additionally, excavation and construction of the foundation will occur during this phase of construction. Site work completed during this stage includes the installation of rock anchors (tiebacks) into the bank on the north side of the project site. Salvaged material will need to be stockpiled for this portion of construction for reuse in later phases.

Phase 2 –

Phase 2 is developed from the existing utilities plan C500. During this stage of construction the placement of the concrete and the erection of steel will occur. The operating radius of the crane is depicted as the circle in red. Additional activities that will occur during this phase are the beginning of the construction of the exterior wall, and the beginning of the rough installation of the MEP systems. Problematic areas for Phase 2 will largely be a result of site congestion/traffic passing through the only site access road while work on that portion of the building is occurring.

Phase 3 –

Phase 3 construction plan is developed from the existing utilities plan C500. The most significant activity represented on this page is the completion of the site. Progression of site work will flow from the north east to south west corners of the site. Important activities occurring during this phase include: MEP Rough-out, partition framing and drywall, installation of building finishes, and commissioning.



NORTH

LEGEND	
	PROPERTY LINE
	EXISTING ADJACENT PROPERTY LINE
	EXISTING RIGHT-OF-WAY
	EXISTING EASEMENT
	EXISTING INDEX CONTOUR
	EXISTING INTERMEDIATE CONTOUR
	EXISTING SANITARY SEWER LINE
	EXISTING OVERHEAD ELECTRIC LINE
	EXISTING GAS LINE
	EXISTING UNPAVED DRIVEWAY
	EXISTING UNPAVED ROADWAY
	EXISTING EDGE OF CONCRETE
	EXISTING EDGE OF PAVEMENT
	EXISTING FENCE
	EXISTING GUIDERAIL
	EXISTING TRAIL
	EXISTING TREE/BRUSH LINE
	EXISTING BUSHES
	EXISTING BUILDING
	EXISTING IRON PIN
	EXISTING MANHOLE
	EXISTING STORM SEWER INLET/CATCH BASIN
	EXISTING UTILITY POLE
	EXISTING UTILITY POLE W/ GUY WIRE
	EXISTING GAS VALVE/METER
	EXISTING WATERLINE VALVE
	EXISTING POST
	EXISTING SIGN
	EXISTING MAILBOX
	EXISTING SIGNAL
	EXISTING BOLLARD
	EXISTING SPOT ELEVATION
	PROPOSED INDEX CONTOUR
	PROPOSED INTERMEDIATE CONTOUR
	PROPOSED WALL
	PROPOSED SPOT ELEVATION
	REINFORCED SOIL SLOPE
	DETAIL NUMBER
	SHEET NUMBER

Traffic Flow


Center for Sustainable Landscapes (CSL)

for:
Phipps Conservatory and Botanical Gardens
One Schenley Park Drive
Pittsburgh, Pa 15213

DATE: 9/23/2011


EXISTING CONDITIONS

DANIEL ZARTMAN



Notes:

- Property lines extend beyond boundaries of plan.
- Non-construction pedestrian / vehicular traffic does not interfere with site.
- Temporary Lighting located on existing utility poles.
- Fire hydrants are not located in the immediate vicinity.
- Worker parking will change frequently. Parking will typically occur at the South Eastern side of the warehouse. And along the south side of the site.






A

B

C


D



- Phase 1:
- Site Demolition
 - Site Excavation
 - Demo/Place Site Utilities (See Existing Conditions Plan)
 - Place Tieback Soil Reinforcement
 - Place Foundations

LEGEND	
	PROPERTY LINE
	EXISTING ADJACENT PROPERTY LINE
	EXISTING RIGHT-OF-WAY
	EXISTING EASEMENT
	EXISTING INDEX CONTOUR
	EXISTING INTERMEDIATE CONTOUR
	EXISTING SANITARY SEWER LINE
	EXISTING OVERHEAD ELECTRIC LINE
	EXISTING GAS LINE
	EXISTING UNPAVED DRIVEWAY
	EXISTING UNPAVED ROADWAY
	EXISTING EDGE OF CONCRETE
	EXISTING EDGE OF PAVEMENT
	EXISTING FENCE
	EXISTING GUIDERAIL
	EXISTING TRAIL
	EXISTING TREE/BRUSH LINE
	EXISTING BUSHES
	EXISTING BUILDING
	EXISTING IRON PIN
	EXISTING MANHOLE
	EXISTING STORM SEWER INLET/CATCH BASIN
	EXISTING UTILITY POLE
	EXISTING UTILITY POLE W/ GUY WIRE
	EXISTING GAS VALVE/METER
	EXISTING WATERLINE VALVE
	EXISTING POST
	EXISTING SIGN
	EXISTING MAILBOX
	EXISTING SIGNAL
	EXISTING BOLLARD
	EXISTING SPOT ELEVATION
	PROPOSED INDEX CONTOUR
	PROPOSED INTERMEDIATE CONTOUR
	PROPOSED WALL
	PROPOSED SPOT ELEVATION
	REINFORCED SOIL SLOPE
	DETAIL NUMBER
	SHEET NUMBER

- Direction of Intended Traffic Flow
- Direction of Work Flow



Center for Sustainable Landscapes (CSL)

for:
Phipps Conservatory and Botanical Gardens
One Schenley Park Drive
Pittsburgh, Pa 15213

DATE: 9/23/2011

Construction Site Plan
Phase 1

DANIEL ZARTMAN




NORTH

A

B

C

D



- Phase 2:
- Erect Steel
 - Place Concrete Slabs
 - Construct Exterior Wall
 - Install Roofing
 - Rough Installation of MEP Systems
 - Continuation of Site Development
 - Operating locations of crane represent the beginning and final location

LEGEND	
	PROPERTY LINE
	EXISTING ADJACENT PROPERTY LINE
	EXISTING RIGHT-OF-WAY
	EXISTING EASEMENT
	EXISTING INDEX CONTOUR
	EXISTING INTERMEDIATE CONTOUR
	EXISTING SANITARY SEWER LINE
	EXISTING OVERHEAD ELECTRIC LINE
	EXISTING GAS LINE
	EXISTING UNPAVED DRIVEWAY
	EXISTING UNPAVED ROADWAY
	EXISTING EDGE OF CONCRETE
	EXISTING EDGE OF PAVEMENT
	EXISTING FENCE
	EXISTING GUIDERAIL
	EXISTING TRAIL
	EXISTING TREE/BRUSH LINE
	EXISTING BUSHES
	EXISTING BUILDING
	EXISTING IRON PIN
	EXISTING MANHOLE
	EXISTING STORM SEWER INLET/CATCH BASIN
	EXISTING UTILITY POLE
	EXISTING UTILITY POLE W/ GUY WIRE
	EXISTING GAS VALVE/METER
	EXISTING WATERLINE VALVE
	EXISTING POST
	EXISTING SIGN
	EXISTING MAILBOX
	EXISTING SIGNAL
	EXISTING BOLLARD
	EXISTING SPOT ELEVATION
	PROPOSED INDEX CONTOUR
	PROPOSED INTERMEDIATE CONTOUR
	PROPOSED WALL
	PROPOSED SPOT ELEVATION
	REINFORCED SOIL SLOPE
	DETAIL NUMBER
	SHEET NUMBER

Direction of Work Flow

Center for Sustainable Landscapes (CSL)

for:
Phipps Conservatory and Botanical Gardens
One Schenley Park Drive
Pittsburgh, Pa 15213

DATE: 9/23/2011

Construction Site Plan
Phase 2

DANIEL ZARTMAN

SCALE IN FEET
0 40 80



NORTH

A

B

C

D

- Phase 3:
- MEP Rough-out
 - Framing and Drywall
 - Install Building Finishes
 - Complete Site Work and Paving
 - Start-Ups, Testing, Inspections, Commissioning

Material Storage

Temp. Power Transformer

CSL Building Footprint

Progression of Site Work

Turner Trailer

Parking

Existing B & G Warehouse to be used for storage of Materials

Tool Trailer

1

2

3

4

5

- LEGEND
- PROPERTY LINE
 - EXISTING ADJACENT PROPERTY LINE
 - EXISTING RIGHT-OF-WAY
 - EXISTING EASEMENT
 - EXISTING INDEX CONTOUR
 - EXISTING INTERMEDIATE CONTOUR
 - EXISTING SANITARY SEWER LINE
 - EXISTING OVERHEAD ELECTRIC LINE
 - EXISTING GAS LINE
 - EXISTING UNPAVED DRIVEWAY
 - EXISTING UNPAVED ROADWAY
 - EXISTING EDGE OF CONCRETE
 - EXISTING EDGE OF PAVEMENT
 - EXISTING FENCE
 - EXISTING GUIDERAIL
 - EXISTING TRAIL
 - EXISTING TREE/BUSH LINE
 - EXISTING BUSHES
 - EXISTING BUILDING
 - EXISTING IRON PIN
 - EXISTING MANHOLE
 - EXISTING STORM SEWER INLET/CATCH BASIN
 - EXISTING UTILITY POLE
 - EXISTING UTILITY POLE W/ GUY WIRE
 - EXISTING GAS VALVE/METER
 - EXISTING WATERLINE VALVE
 - EXISTING POST
 - EXISTING SIGN
 - EXISTING MAILBOX
 - EXISTING SIGNAL
 - EXISTING BOLLARD
 - EXISTING SPOT ELEVATION
 - PROPOSED INDEX CONTOUR
 - PROPOSED INTERMEDIATE CONTOUR
 - PROPOSED WALL
 - PROPOSED SPOT ELEVATION
 - PROPOSED GAS LINE
 - PROPOSED UNDERGROUND ELECTRIC
 - PROPOSED UTILITY POLE
 - PROPOSED TRANSFORMER PAD
 - RELOCATED GAS METER

Direction of Work Flow through interior spaces

Material access points to interior spaces

SCALE IN FEET

0 40 80

Center for Sustainable Landscapes (CSL)

for:

Phipps Conservatory and Botanical Gardens

One Schenley Park Drive

Pittsburgh, Pa 15213

DATE: 9/23/2011

Construction Site Plan

Phase 3

Daniel Zartman

Local Conditions

The construction site is located in a large park, in a residential neighborhood. The main vehicular access road to the site is located on a main thoroughfare through the neighborhood leading towards downtown Pittsburgh. The site is of an average size relative to the building's footprint. The only neighboring building to the site is also owned by the owner, Phipps Conservatory. Parking is currently available for all trades onsite, and will remain that way for the entirety of the project. Designated parking locations can be viewed on the preceding phasing plans.

Since this is a sustainable construction site, a large amount of recycling and sorting will occur on site prior to removal. Local tipping fees are \$31.00 per ton for trash, and \$40 per ton for recyclables.

According to the USDA, Natural Resources Conservation Service soil survey, the soils at the site belong to the Urban Land-Rainsboro and the Gilpin-Uphsur series. Soils consist primarily of residual soil weathered from sandstone, siltstone, and shale. The water level was not obtainable as all 35 of the boring samples were recorded as being dry. The deepest recorded depth sampled was 35 feet, as a result no dewatering is necessary.

Local preferred construction methods that are typical to that of the Pittsburgh region include: steel, masonry, and concrete buildings. For sustainable construction projects, it is more favorable to use steel to contribute to attaining LEED certification as its use increases the percentage of recycled content used on the project.

Client Information/Project information



Built in 1893, the original Phipps Conservatory and Botanical Gardens is a cultural icon to the Greater Pittsburgh area. Located in Schenley Park near downtown Pittsburgh, Phipps operates as a non-profit with an intense focus on education on the importance and beauty of plants. Phipps has been noticing sizable growth and an

increase in national and international attention, as it was the host for the opening dinner of the 2009 G-20 Summit in Pittsburgh. With this surge of attention, the conservatory has invested in a campus wide development and focused on increasing its national image. The image above is a view of the entrance and the original Phipps greenhouse.

Phipps is expanding to offer more educational services by creating a 24,000 GSF mixed use classroom and research building. The most significant expectations of the project by the owner is that the building is built with sustainability in mind, and achieves all three sustainable design certifications sought. Sustainability is what Phipps preaches, and the purpose of this building, aside from growth and development, is largely increasing awareness for sustainability.

There are almost no externalities affecting work on this project. Site access and size are suitable for the scale of the building footprint and project. The site that the building is going to inhabit is currently not in use, and thus no phased or dual occupancy requirements are needed. Minor inconveniences include the relocation of a few select utilities and the demolition of a portion of an existing warehouse.

Project Delivery System

The CSL was delivered via traditional design-bid-build approach. This approach was chosen because it is a well known project delivery system amongst local contractors. Furthermore, utilizing a design-bid-build delivery system allowed the owner to lock-in a price, prior to the start of construction (making an exception to change orders). The contractor was selected for this project through a private bid proposal. The contractor, having worked with the owner in the past, utilized knowledge gained from past experiences to their advantage. For the bid, a Bid Bond of 5% of the contracted value was required. The successful bidder was also required to furnish both a Performance Bond and Payment Bond for 100% of the contracted amount upon award. In addition, the successful bidder must also furnish an AIA document A305 Contractor's Qualification Statement.

Turner also operates a contractor controlled insurance program, which requires the prequalification of subcontractors and that they furnish and maintain Builder's Risk Insurance. Turner requires that subcontractors hold Workers' Comp., Employers' Liability Insurance, and Commercial General Liability Insurance. Upon acceptance of a subcontract, Turner also requires each subcontractor to supply a Performance and Payment Bond for the project.

In Figure 7 (Page 20), the project organizational chart is shown. Contracts between all parties are Lump Sum. In the chart, solid lines depict contractual obligations while dotted lines represent lines of communication. Contract types are all typical AIA General Contract and Subcontract documents. Contractually, this project is unique in the owner holds independent subcontractors.

Traditional design-bid-build is not the most ideal for the construction of this project. With such a constrained budget and an existing relationship with the owner, a design-build contract could have been more beneficial. Increased collaboration and planning could have saved the owner significant money while increasing project value. Constructability could have been considered as a more serious design factor. Currently, complications are increasing with the specified construction of a cast-in-place concrete stair, an issue that should have never occurred.

Project Team Organizational Chart
Center for Sustainable Landscapes




Figure 7: CSL Project Organizational Chart

Staffing Plan

Due to the smaller contract size of the CSL, the optimum size staffing team is notably smaller than the majority of other Turner Projects. Figure 8 shows is the organizational chart of the project team. Due to the projects smaller size, managers are forced to express expertises in a larger range of construction practices. Of the staff listed below: Bill Beck, Dareen Romanchik, and Megan Corrie are located onsite. Relative to other projects of this size, the staffing team is large; this is due to the large amount of paperwork associated with the coordination needed for the addition sustainable systems and goals included in the project.




Figure 8: Turner Project Organizational Staffing Chart

Appendix A:
RS Means Square Foot Estimate

Square Foot Cost Estimate Report

Estimate Name: **Center for Sustainable Landscapes**

Building Type: **College, Classroom, 2-3 Story with Decorative Concrete Block / Steel Frame**
 Location: **PITTSBURGH, PA**
 Stories Count (L.F.): **3.00**
 Stories Height: **14.00**
 Floor Area (S.F.): **24,350.00**
 LaborType: **Open Shop**
 Basement Included: **No**
 Data Release: **Year 2011**
 Cost Per Square Foot: **\$158.50**
 Total Building Cost: **\$3,859,500**



Costs are derived from a building model with basic components. Scope differences and market conditions can cause costs to vary significantly.
Parameters are not within the ranges recommended by RSMMeans.

		% of Total	Cost Per SF	Cost
A Substructure		2.7%	3.96	\$96,500
A1010	Standard Foundations		0.39	\$9,500
	Spread footings, 3000 PSI concrete, load 150K, soil bearing capacity 6 KSF, 5' - 6" square x 18" deep			
	Spread footings, 3000 PSI concrete, load 300K, soil bearing capacity 6 KSF, 7' - 6" square x 25" deep			
A1030	Slab on Grade		1.52	\$37,000
	Slab on grade, 4" thick, non industrial, reinforced			
A2010	Basement Excavation		0.08	\$2,000
	Excavate and fill, 100,000 SF, 4' deep, sand, gravel, or common earth, on site storage			
A2020	Basement Walls		1.97	\$48,000
	Foundation wall, CIP, 4' wall height, direct chute, .099 CY/LF, 4.8 PLF, 8" thick			
	Foundation wall, CIP, 4' wall height, direct chute, .148 CY/LF, 7.2 PLF, 12" thick			
B Shell		27.0%	39.20	\$954,500
B1010	Floor Construction		15.93	\$388,000
	Steel column, W10, 150 KIPS, 16' unsupported height, 45 PLF			
	Steel column, W12, 300 KIPS, 16' unsupported height, 72 PLF			
	Floor, composite metal deck, shear connectors, 5.5" slab, 35'x35' bay, 29.5" total depth, 75 PSF superimposed load,			
	Fireproofing, gypsum board, fire rated, 3 layer, 1.5" thick, 10" steel column, 3 hour rating, 27 PLF			
	Fireproofing, gypsum board, fire rated, 3 layer, 1.5" thick, 14" steel column, 3 hour rating, 35 PLF			
B1020	Roof Construction		2.98	\$72,500
	Floor, steel joists, beams, 1.5" 22 ga metal deck, on columns, 35'x35' bay, 25" deep, 30 PSF superimposed load, 52			
	Floor, steel joists, beams, 1.5" 22 ga metal deck, on columns, 35'x35' bay, 25" deep, 30 PSF superimposed load, 52			
B2010	Exterior Walls		7.25	\$176,500
	Concrete block (CMU) wall, split rib, 8 ribs, hollow, regular weight, 8x8x16, reinforced, vertical #5@32", grouted			
B2020	Exterior Windows		10.27	\$250,000
	Aluminum flush tube frame, for 1/4" glass, 1-3/4"x4", 5'x6' opening, no intermediate horizontals			
	Glazing panel, plate glass, 1/4" thick, clear			
B2030	Exterior Doors		0.60	\$14,500
	Door, aluminum & glass, with transom, narrow stile, double door, hardware, 6'-0" x 10'-0" opening			

		% of Total	Cost Per SF	Cost
B3010	Roof Coverings		2.18	\$53,000
	Roofing, asphalt flood coat, gravel, base sheet, 3 plies 15# asphalt felt, mopped			
	Insulation, rigid, roof deck, composite with 2" EPS, 1" perlite			
	Roof edges, aluminum, duranodic, .050" thick, 6" face			
	Flashing, aluminum, no backing sides, .019"			
	Gravel stop, aluminum, extruded, 4", mill finish, .050" thick			
C Interiors		21.3%	30.92	\$753,000
C1010	Partitions		3.88	\$94,500
	Concrere block (CMU) partition, light weight, hollow, 6" thick, no finish			
C1020	Interior Doors		5.01	\$122,000
	Door, single leaf, kd steel frame, hollow metal, commercial quality, flush, 3'-0" x 7'-0" x 1-3/8"			
C1030	Fittings		4.62	\$112,500
	Chalkboards, liquid chalk type, wood frame & chalktrough			
	Cabinets, school, counter, wood, 32" high			
C2010	Stair Construction		2.85	\$69,500
	Stairs, steel, cement filled metal pan & picket rail, 20 risers, with landing			
C3010	Wall Finishes		4.13	\$100,500
	2 coats paint on masonry with block filler			
	Painting, masonry or concrete, latex, brushwork, primer & 2 coats			
	Painting, masonry or concrete, latex, brushwork, addition for block filler			
	Ceramic tile, thin set, 4-1/4" x 4-1/4"			
C3020	Floor Finishes		4.58	\$111,500
	Carpet, tufted, nylon, roll goods, 12' wide, 36 oz			
	Carpet, padding, add to above, maximum			
	Vinyl, composition tile, minimum			
	Vinyl, composition tile, maximum			
	Tile, ceramic natural clay			
C3030	Ceiling Finishes		5.85	\$142,500
	Acoustic ceilings, 3/4" mineral fiber, 12" x 12" tile, concealed 2" bar & channel grid, suspended support			
D Services		48.7%	70.72	\$1,722,000
D1010	Elevators and Lifts		5.48	\$133,500
	1 - Hydraulic, passenger elevator, 2500 lb, 2 floors, 100 FPM			
	Hydraulic passenger elevator, 2500 lb., 2 floor, 125 FPM			
D2010	Plumbing Fixtures		14.50	\$353,000
	Water closet, vitreous china, bowl only with flush valve, wall hung			
	Urinal, vitreous china, wall hung			
	Lavatory w/trim, wall hung, vitreous china, 19" x 17"			
	Lab sink w/trim, polyethylene, single bowl, double drainboard, 54" x 24" OD			
	Service sink w/trim, vitreous china, wall hung 22" x 20"			
	Water cooler, electric, wall hung, wheelchair type, 7.5 GPH			
D2020	Domestic Water Distribution		2.18	\$53,000
	Gas fired water heater, commercial, 100< F rise, 600 MBH input, 576 GPH			
D2040	Rain Water Drainage		0.53	\$13,000
	Roof drain, CI, soil, single hub, 6" diam, 10' high			
	Roof drain, CI, soil, single hub, 6" diam, for each additional foot add			
D3050	Terminal & Package Units		17.25	\$420,000
	Roof top, multizone, air conditioner, schools and colleges, 25,000 SF, 95.83 ton			
D4010	Sprinklers		2.63	\$64,000
	Wet pipe sprinkler systems, steel, light hazard, 1 floor, 10,000 SF			
	Wet pipe sprinkler systems, steel, light hazard, each additional floor, 10,000 SF			

		% of Total	Cost Per SF	Cost
D4020	Standpipes		0.27	\$6,500
	Dry standpipe risers, class III, steel, black, sch 40, 6" diam pipe, 1 floor			
	Dry standpipe risers, class III, steel, black, sch 40, 6" diam pipe, additional floors			
D5010	Electrical Service/Distribution		8.93	\$217,500
	Service installation, includes breakers, metering, 20' conduit & wire, 3 phase, 4 wire, 120/208 V, 2000 A			
	Feeder installation 600 V, including RGS conduit and XHHW wire, 2000 A			
	Switchgear installation, incl switchboard, panels & circuit breaker, 2000 A			
D5020	Lighting and Branch Wiring		11.95	\$291,000
	Receptacles incl plate, box, conduit, wire, 10 per 1000 SF, 1.2 W per SF, with transformer			
	Wall switches, 1.0 per 1000 SF			
	Miscellaneous power, 1.2 watts			
	Central air conditioning power, 4 watts			
	Motor installation, three phase, 460 V, 15 HP motor size			
	Motor feeder systems, three phase, feed to 200 V 5 HP, 230 V 7.5 HP, 460 V 15 HP, 575 V 20 HP			
	Fluorescent fixtures recess mounted in ceiling, 2.4 watt per SF, 60 FC, 15 fixtures @ 32 watt per 1000 SF			
D5030	Communications and Security		6.34	\$154,500
	Communication and alarm systems, includes outlets, boxes, conduit and wire, sound systems, 30 outlets			
	Communication and alarm systems, fire detection, addressable, 25 detectors, includes outlets, boxes, conduit and w			
	Fire alarm command center, addressable with voice, excl. wire & conduit			
	Communication and alarm systems, includes outlets, boxes, conduit and wire, master clock systems, 20 rooms			
	Communication and alarm systems, includes outlets, boxes, conduit and wire, master TV antenna systems, 30 outle			
	Internet wiring, 8 data/voice outlets per 1000 S.F.			
D5090	Other Electrical Systems		0.66	\$16,000
	Generator sets, w/battery, charger, muffler and transfer switch, gas/gasoline operated, 3 phase, 4 wire, 277/480 V, 1			
E Equipment & Furnishings		0.3%	0.37	\$9,000
E1090	Other Equipment		0.37	\$9,000
	3 - Detection Systems, smoke detector, duct type, excl. wires & conduit			
	1 - Hydraulic Passenger Elevators, for number of stops over 2, add			
F Special Construction		0.0%	0.00	\$0
G Building Sitework		0.0%	0.00	\$0
Sub Total		100%	\$145.17	\$3,535,000
Contractor's Overhead & Profit		6.0%	\$8.71	\$212,000
Architectural Fees		3.0%	\$4.62	\$112,500
User Fees		0.0%	\$0.00	\$0
Total Building Cost			\$158.50	\$3,859,500

Appendix B:
RS Means Assemblies Estimate

Assembly Detail Report

Pittsburgh,

Year 2011

Date: 21-Sep-11

Prepared By:

Daniel Zartman

Assembly Estimate

State University AE Department Student

Assembly Number		Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
D Services						
D2000000000			1.00			\$0.00
D20101203000		Water closets, battery mount, wall hung, back to back, first pair of closets	2.00	Ea.	\$3,511.07	\$7,022.14
D20101203100		Water closets, battery mount, wall hung, each additional pair of closets, back to back	6.00	Ea.	\$3,470.99	\$20,825.94
D20102102000		Urinal, vitreous china, wall hung	4.00	Ea.	\$1,208.05	\$4,832.20
D20103102080		Lavatory w/trim, wall hung, PE on CI, 19" x 17"	16.00	Ea.	\$1,483.31	\$23,732.96
D20104201800		Laundry sink w/trim, PE on CI, black iron frame, 24" x 23" single compartment	1.00	Ea.	\$1,493.28	\$1,493.28
D20104301800		Lab sink w/trim, polyethylene, single bowl, flanged, 18-1/2" x 18-1/2" OD	6.00	Ea.	\$1,238.32	\$7,429.92
D20108101920		Drinking fountain, 1 bubbler, wall mounted, non recessed, stainless steel, no back	4.00	Ea.	\$1,642.74	\$6,570.96
D20202402020		Electric water heater, commercial, 100< F rise, 200 gal, 120 KW 490 GPH	1.00	Ea.	\$28,157.40	\$28,157.40
D20202952600		Solar, closed loop, immersed exchanger, 1/2" tubing, 4 each 4' x 4'-4" vacuum tube collectors, 120 gal	2.00	Ea.	\$11,699.73	\$23,399.46
D30000000000			0.00			\$0.00
D30106842560		Solar passive heating, direct gain, 2'-6" x 5', double glazed window, one panel wide	75.00	Ea.	\$1,012.39	\$75,929.25
D30201041360		Large heating systems, electric boilers, hydronic, 26,100 SF, 420 KW, 1,432 MBH, 4 floors	24,350.00	S.F.	\$8.43	\$205,270.50
D30501553960		Rooftop, multizone, air conditioner, offices, 25,000 SF, 79.16 ton	24,350.00	S.F.	\$14.69	\$357,701.50
D40000000000			1.00			\$0.00
D40103100600		Dry pipe sprinkler systems, steel, light hazard, 1 floor, 5000 SF	6,230.00	S.F.	\$4.29	\$26,726.70
D40104100620		Wet pipe sprinkler systems, steel, light hazard, 1 floor, 10,000 SF	18,000.00	S.F.	\$3.00	\$54,000.00
D50000000000			1.00			\$0.00
D50101200360		Service installation, includes breakers, metering, 20' conduit & wire, 3 phase, 4 wire, 120/208 V, 600 A	1.00	Ea.	\$11,918.28	\$11,918.28
D50102300360		Feeder installation 600 V, including RGS conduit and XHHW wire, 600 A	100.00	L.F.	\$166.38	\$16,638.00
D50102400240		Switchgear installation, incl switchboard, panels & circuit breaker, 600 A	1.00	Ea.	\$17,895.05	\$17,895.05
D50201150200		Receptacle systems, underfloor duct, 5' on center, low density	24,350.00	S.F.	\$9.30	\$226,455.00
D50201300280		Wall switches, 2.0 per 1000 SF	24,350.00	S.F.	\$0.42	\$10,227.00
D50202080600		Fluorescent fixtures, type A, 17 fixtures per 1000 SF	24,350.00	S.F.	\$7.23	\$176,050.50
D50303100240		Telephone systems, underfloor duct, 5' on center, high density	22,000.00	S.F.	\$12.92	\$284,240.00
D50309100452		Communication and alarm systems, fire detection, addressable, 25 detectors, includes outlets, boxes, conduit and wire	12.00	Ea.	\$18,307.30	\$219,687.60
D50309200106		Internet wiring, 6 data/voice outlets per 1000 S.F.	22.00	M.S.F.	\$1,660.56	\$36,532.32
D50904300100		Photovoltaic power system, grid connected 10kW AC and DC loads	0.00	Ea.	\$92,281.90	\$0.00

Assembly Number			Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
--------------------	--	--	-------------	----------	------	--------------------	-------------------------

D Services Subtotal

\$1,842,735.96